


External "Pop-Action" Pressure Relief Valves for ASME Containers and Bulk Plant Installations AA3126, AA3130, 3131, 3132, 3133, 3135, AA3135, and A3149 Series

Designed for use as a primary relief valve on ASME above ground and underground containers, bulk plant installations and skid tanks. The 3131 Series may also be used as a primary or secondary relief valve on DOT cylinders, or as a hydrostatic relief valve. All working components of these relief valves are outside the container connection, so the valves must be protected from physical damage.



Ordering Information

Part Number	Start To Discharge Setting PSIG	Container Connection M. NPT	Overall Height (Approx.)	Wrench Hex Section	Flow Capacity SCFM/Air (a)		Suitable for Tanks w/ Surface Area Up To: (e)	Accessories			
					UL (At 120% of Set Pressure)	ASME (At 120% of Set Pressure)		Protective Cap	Pipe Away Adapter		Weep Hole Deflector
									Part Number	Outlet Size	
AA3126L030	30	½"	2⅝"	⅞"	(b)	-	-	7545-40	AA3126-10	½" M. NPT	-
A3149L55	55	2½"	10½"	4⅞"	2608(c)	-	113 Sq. Ft.	3149-40	(h)		Included (j)
A3149L200	200				8770 (c)	-	500 Sq. Ft.				
AA3126L250	250	½"	2⅝"	⅞"	277 (c)	-	23 Sq. Ft. (f)	7545-40	AA3126-10	½" M. NPT	-
3131G		¾"	37/16"	1¼"	2060	1939	85 Sq. Ft.	3133-41g	-		
AA3130UA250			2045		1838	249 Sq. Ft. (f)	AA3130-40P	AA3131-10	1" F. NPT		
AA3130A250			-		1706 (10 OP)	-	AA3130-40P				
T3131G			2060		1939	85 Sq. Ft.	3131-54				
W3132G		1"	6 1/32"	2⅜"	3340	-	154 Sq. Ft.	3132-54 (g)	3132-10	1¼" F. NPT	3133-B
3132G		4130			-	200 Sq. Ft.	-				
T3132G		3790			-	180 Sq. Ft.	3132-10		1¼" F. NPT		
MV3132G		3995			-	190 Sq. Ft.	-				
3135G		1¼"	5 21/32"	2 11/16"	5770	5549	300 Sq. Ft.	3135-54 (g)	3135-10	2" F. NPT	-
AA3135UA250	6 13/32"		6430		6341	1010 Sq. Ft. (f)	AA3135-0PR	AA3135-10			
3133G		1½"	5 15/16"	3⅝"	6080	-	320 Sq. Ft.	3133-41g	3133-10		3133-11B
A3149G		2½"	10½"	4⅞"	10390	9153	613 Sq. Ft.	3149-40	(h)		Included (j)
AA3130UA265	265	¾"	37/16"	1¼"	2125	1912	261 Sq. Ft. (f)	AA3130-40P	AA3131-10	1" F. NPT	-
AA3135UA265		1¼"	6 13/32"	2 11/16"	6615	6703	1045 Sq. Ft. (f)	AA3135-40PR	AA3135-10	2" F. NPT	-
AA3126L312	312	½"	2⅝"	⅞"	330 (c)	-	27 Sq. Ft. (f)	7545-40	AA3126-10	½" M. NPT	-

(a) Flow rates shown are for bare relief valves. Adapters and pipeaways will reduce flow as discussed in forewording information.
 (b) Not UL or ASME rated. .059 square inch effective area.
 (c) Not UL or ASME rated. REGO® rated at 120% of set pressure.

(f) Per ANSI K61.1-1972, Appendix A.
 (g) Cap supplied with chain.
 (h) Outlet 3/2-8N (F) thread, will accept 3" M. NPT pipe thread.
 (j) Weep hole deflector is Part No. A3134-11B.


(e) Per NFPA Pamphlet #58, Appendix D. Area shown is for UL or ASME flow rating—whichever is larger.

External "Pop-Action" Supplementary Pressure Relief Valves for Small ASME Containers and DOT Cylinders 3127 and 3129 Series

Designed for use as a supplementary relief valve on small ASME above ground and underground containers. They may also be used as a primary or secondary relief device on DOT cylinders, or as hydrostatic relief valves.

All working components of these relief valves are outside the container connection, so the valves must be protected from physical damage.

3129-10 Pipe Away Adapter



Ordering Information

Part Number	Container Type	Start To Discharge Setting PSIG	Container Connection M. NPT	Overall Height (Approx.)	Wrench Hex Section	Flow Capacity SCFM/Air		Suitable for Tanks w/ Surface Area Up To:*	Accessories		
						UL (At 120% of Set Pressure)	REGO® Rated at 480 PSIG***		Protective Cap	Pipeaway Adapter	
3127G	ASME	250	1/4"	1 31/32"	7/8"	295	-	-	7545-40	3129-10	1/2" F. NPT
3129G			1/2"	2 19/32"	1 1/8"	465	-	-			
3127K	DOT	375	1/4"	1 31/32"	7/8"	-	450	100 lbs. /Propane		3129-10	1/2" F. NPT
3129K			1/2"	2 19/32"	1 1/8"	-	780	200 lbs. /Propane			

* Flow rates shown are for bare relief valves. Adapters and pipeaways will reduce flow as discussed in forewording information.

** Not UL or ASME rated. REGO® rated at 480 PSIG.

*** Meets DOT requirements.